

<b>DETAILED TYPE OF WORK PROPOSED</b>
---------------------------------------

<b>1 - masonry/demolition</b>
-------------------------------

*Soil protection*

*Demolition of a partition between the bedroom and the kitchen with removal of the door (kept for resting)*

*In the type 4 studios demolition of a partition between the bedroom and the living room*

*Removal of earthenware, tiles, headboard, furniture and kitchen sink as well as the demolition of a concrete base.*

*Removal of earthenware, tiles and fixtures in the bathroom*

*Removal of rubble*

*Creation of an opening between the kitchen and the main room with the installation of a new window frame.*

*Installation of a hydro plaster tile wall between the bedroom and the kitchen*

*Wall lining in BA13 hydro in the kitchen and bathroom + renovation of the screeds*

*Supply and installation of 30x30 lead gray tiles in the kitchen and 20x20 satin white tiles in the bathroom.*

*Supply and installation of a new earthenware 15x15 gray in the kitchen and 15x15 taupe in the bathroom*

<b>2- plumbing/heating and ventilation</b>
--

*Putting out of water of the whole installation before demolition by the mason*

*Removal and installation of radiators after painting*

*Rehabilitation of networks*

<i>Supply and installation of a single stainless steel sink + a drainer and a sink mixer tap (type Grohe high spout Bauloop) in the kitchen.</i>
<i>Supply and installation in the bathroom of a suspended toilet (Geberit type), a 120x80 shower tray with a mixer tap (Grohe Eurosmart type) and a shower bar (Grohe Tempesta 2 type), a complete vanity unit (Ideal Standard type in 50 on legs) with an illuminated mirror, a basin mixer tap (Grohe Eurosmart type) and a shower curtain set with support.</i>
<i>Supply and installation of new high and low ventilation grilles in the kitchen and bathroom</i>
<b>3- carpentry</b>
<i>Supply of a frame and rest of the door kept between the kitchen and the living room</i>
<i>Supply and installation of a sliding door set to be painted with counter partition, reception post and top strip in the type 1 studios</i>
<i>Supply and installation in the kitchen of a cabinet under the sink, a base cabinet, an upper cabinet with microwave support and a worktop with cut-outs for the sink and hob.</i>
<i>Supply and installation of white melamine shelves on racks and brackets in the kitchen</i>
<i>Supply and installation of medium shelves on racks and adjustable brackets in the storage area.</i>
<i>Supply and installation of baseboards and cladding to be painted following various modifications</i>
<i>Supply and installation of 4 aluminium door bottom protectors and threshold bars as well as the verification and installation of all the joinery</i>
<i>Supply and installation of coat hooks in the bathroom</i>
<i>Supply and installation of doorstops</i>

<b>4- electricity</b>
<i>Installation of a construction site box</i>
<i>Creation of new lines in the kitchen for the refrigerator, hob, microwave, electrical outlets and two light points (trenches and moldings)</i>
<i>Creation of new lines in the bathroom for two light points and an electrical outlet (trenches and mouldings)</i>
<i>Creation of new lines in the room for a light point and two outlets (trenches and mouldings)</i>
<i>Moving the phone jack</i>
<i>Modification of the electrical panel: addition of 10A/16A/20A circuit breakers</i>
<i>Supply and installation of a wall light (Thorn Starlette type) and a porthole (Thorn type) in the kitchen, a porthole (Thorn type) in the bedroom, the entrance, the storage room and the bathroom, a double ignition switch in the kitchen, the bathroom and the living room, a smoke detector in the living room and the replacement of all the sockets and switches of the workshop type Legrand Nilo2 built-in.</i>
<i>Supply and installation of household appliances in the kitchen (1 ceramic hob 2 fireplaces, 1 built-in microwave and 1 table top refrigerator in 60 cm type Ikea)</i>
<i>Installation of new lighting in the living room (a rail with 3 led spots and a row of fluorescent tubes on the work panel)</i>
<i>Checks of the entire electrical installation</i>
<b>5- painting and flooring</b>

<i>Supply and application of one coat of primer, double coating, sanding and application of 2 coats of satin white paint on walls and radiators, 2 coats of matt white paint on all ceilings and 2 coats of satin grey paint on baseboards and door frames and 2 coats of grey floor paint in large DUPLEX workshops.</i>
<i>Supply and installation of a 49x99 PVC slab floor covering (type Tarkett Rough Concrete-White ref : 24363157) : intervention in sub-section 4</i>